

BEFORE YOU BUY – UNDERSTAND THE REQUIREMENTS OF BOSTON FD TCM3-51725!!

Boston FD TCM3-51725 requires a pressurized alarm system for all standpipes in buildings under construction or demolition. The requirements of this law are specific and detailed. Some firms are attempting to provide equipment without fully understanding all of these details. BEFORE YOU BUY, compare what others are offering to **STANDPIPE-PAC** from **UNITED** Fire Systems...

BOSTON FD TCM3-51725 REQUIREMENTS

ITEM	STANDPIPE-PAC	OTHERS
Air Compressor	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
Pressure Switch Operating on Pressure Drop	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
Local Audible Signal	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
Automatic Compressor Cut-In and Cut-Out	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
Air Dryer	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Pressure Switch Operating Over 25 PSIG	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Manual Air Release Device Included	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Active, Dedicated Power Supply	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Check Valve (prevents water from reaching compressor)	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Lockable Shutoff Valve	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Remote Weatherproof Audible / Amber Visual Signal	<input checked="" type="checkbox"/>	<input type="checkbox"/>

ADDITIONAL IMPORTANT AND VALUABLE FEATURES

ITEM	STANDPIPE-PAC	OTHERS
Provision for Additional Audible Alarm Devices (may be required by Boston FD)	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Silenceable Audible Devices (allows signals to be silenced after notification and response)	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Supervision of Audible Devices (provides warning if wiring is damaged)	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Batteries for Power Backup (system still operates for 24 hours minimum if power fails)	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Local Air Pressure Gage (visual indication of system status at a glance)	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Compressor Power Disconnect Switch (permits control of compressor operation as needed)	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Digital Communicator (allows notification to site safety office or central station)	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Fully Factory Assembled and Tested (no field assembly required)	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Built-In Test / Service Device (allows easy, fast testing of signals PLUS safe de-pressurization for service)	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Included Auxiliary Condensate Drain Device (to help prevent water blockage)	<input checked="" type="checkbox"/>	<input type="checkbox"/>

STANDPIPE-PAC provides you everything you need for Boston FD TCM3-51725 compliance – with additional important features you should not be without. Trust **UNITED** Fire Systems to help you comply!!



UNITED Fire Systems
 Division of United Fire Protection Corporation
 1 Mark Road
 Kenilworth, NJ 07033
 Phone: 908-688-0300 Fax: 908-688-0218
www.unitedfiresystems.net

